

DOCUMENT RESUME

ED 378 858

HE 028 005

AUTHOR Casey, John M.
TITLE Evaluating Deficiencies in Campus Facilities: The Institutional Research/Physical Plant Nexus.
PUB DATE 11 Oct 90
NOTE 25p.; Paper presented at the Meeting of the Southern Association for Institutional Research and the Society for College and University Planning (Fort Lauderdale, FL, October 11, 1990). For a related paper, see HE 028 004.
PUB TYPE Reports - Research/Technical (143) -- Speeches/Conference Papers (150)
EDRS PRICE MF01/PC01 Plus Postage.
DESCRIPTORS *Capital; Capital Outlay (for Fixed Assets); *College Buildings; Educational Facilities; Educational Finance; Facility Case Studies; Facility Improvement; Facility Inventory; Facility Requirements; Higher Education; Life Cycle Costing; Needs Assessment; State Colleges
IDENTIFIERS Building Maintenance; Facilities Audits; *Facility Evaluation; *University of Georgia

ABSTRACT

The University of Georgia (UG) conducted a complete campus building condition evaluation survey in 1989 that identified the nature and magnitude of the capital renewal/deferred maintenance requirements for each campus building. The survey design was based on a model developed by Harlan Bareither at the University of Illinois. Data were collected at weekly meetings held for 3 hours each over several months. The dollar value of all necessary capital renewal and deferred maintenance work was estimated on a building by building basis. The total analysis covered 1,118 buildings comprising over 11 million square feet. The estimate for each building was compared to the total replacement value of the building and the resultant percentage deficiency was recorded. Results found that: (1) roof and window replacements totaled almost \$19 million; (2) new fixed equipment and elevators totaled over \$36 million; (3) plumbing and fire protection waste piping and sprinkler systems totaled over \$22 million; (4) replacement of heating, ventilating and air conditioning systems equipment and controls accounted for almost \$79 million; and (5) new distribution wiring and fire alarms were estimated at \$22 million. The analysis also noted that under a formula funding system like the one UG uses, the total deficiency of almost 30 percent cannot be corrected with the planned yearly funding level of .75 percent of total replacement cost. (Contains 43 references.) (JB)

* Reproductions supplied by EDRS are the best that can be made *
* from the original document. *

ED 378 858

Evaluating Deficiencies in Campus Facilities:
The Institutional Research/Physical Plant Nexus

Prepared for the 1990 SAIR/SCUP Conference
Southern Association for Institutional Research
Society for College and University Planning

Fort Lauderdale, Florida

October 11, 1990



The University of Georgia

Prepared by
John M. Casey, P.E.
Manager, Physical Plant Engineering Department

U.S. DEPARTMENT OF EDUCATION
Office of Educational Research and Improvement
EDUCATIONAL RESOURCES INFORMATION
CENTER (ERIC)

- ☒ This document has been reproduced as
received from the person or organization
originating it.
☐ Minor changes have been made to improve
reproduction quality.

* Points of view or opinions stated in this docu-
ment do not necessarily represent official
OERI position or policy.

PERMISSION TO REPRODUCE THIS
MATERIAL HAS BEEN GRANTED BY

John M. Casey

TO THE EDUCATIONAL RESOURCES
INFORMATION CENTER (ERIC)."

NE 028 005-

Introduction

Higher education institutions require buildings of all types to support teaching, research and public service activities. These facilities must first be built, and then maintained, to remain useful for their intended purposes. Some maintenance expenses, including funds for functional improvements to spaces and systems, can be deferred for long periods of time. During the 1960s and 70s, many institutions diverted maintenance funds to other "higher priority" projects, including recruiting the world-class researcher and paying for the increased fuel and energy costs resulting from the Arab oil embargo. Since most buildings on a typical university campus were built between 1950 and 1975, deferring this maintenance was rationalized quite easily, since these buildings were "new" and major maintenance projects could be put off until "later". By the late 1970s, higher education administrators, usually the physical plant or business office directors, began calling attention to this deferred maintenance problem, and asked for assistance before conditions escalated from outrageously expensive to prohibitively expensive. Unfortunately, the recession and stock market loss experienced in the 1980s, the reduction in funding for higher education programs by the Federal Government, and the implementation of new regulations involving asbestos abatement

and access for the handicapped, exacerbated this deferred maintenance dilemma. Older institutions also were faced with additional costs due to historic preservation requirements, which impose significantly higher repair and renovation expenditures on an institution's shrinking budget. Operating under retrenchment management principles, college and university administrators once again opted to defer maintenance and functional improvement programs until "later".

During the last few years, the higher education literature has discussed this problem, and concluded that extreme funding difficulties exist for capital renewal and deferred maintenance projects in the academy. All authors agree that each institution should first conduct an audit of its facilities, in order to establish the extent of the problem on each campus. This paper presents the results of a complete campus building condition evaluation survey conducted at the University of Georgia in 1989. This program identified the nature and magnitude of the capital renewal/deferred maintenance requirements for each campus building. The Departments of Institutional Research and Physical Plant combined efforts to implement this evaluation, utilizing a deficiency model that expresses needs as percentages of building replacement costs. The resultant data is important for planning and budgeting purposes, since specific facility problems can be identified and prioritized.

Definitions

Preventive Maintenance - Preventive or normal maintenance is a systematic day-to-day process funded by the annual operating budget to control deterioration of the plant facilities: e.g. structures, systems, equipment, pavement and grounds. Planned maintenance includes scheduled repetitive work to provide adjustments and make minor repairs, and call-in requests for service.(1)

Deferred Maintenance - Deferred maintenance projects include those from prior years and the current year that were not included in the maintenance process because of perceived lower priority status than those projects implemented within available funding. Deferred maintenance includes postponed renewal and replacement maintenance, and unperformed and unscheduled major maintenance.(2)

Renewal and Replacement Maintenance - This refers to a systematic management process to plan and budget for known future cyclic repair and replacement requirements which extend the life and retain usable condition of campus facilities and systems, and which are not normally contained in the annual operating budget. This category includes major activities that have a maintenance cycle in excess of one year: e.g. replace roofs, paint buildings, resurface roads, replace equipment (boilers, chillers, transformers), etc.(3)

Facilities Renewal Program - A facilities renewal program integrates a regular maintenance program funded by current operating funds with deferred maintenance, facilities remodeling and renovations, retrofit for energy conservation, elimination of health and life safety problems, and provisions for access for the handicapped.⁽⁴⁾ Note that, as a practical matter, this definition by Dr. Kaiser includes preventive maintenance because it is almost impossible to separate "that which is maintenance only" from remodeling, renovation and retrofit projects.

Capital Renewal/Deferred Maintenance - The term now generally used in the academy describes the functional improvements and deferred maintenance requirements of a facility; it is essentially the Kaiser "Facilities Renewal" definition without the preventive or normal maintenance components.

National Survey

A 1989 survey⁽⁵⁾ by the National Association of College and University Business Officers (NACUBO) and the Association of Physical Plant Administrators (APPA) indicated that higher education buildings nationwide face a 60 to 70 billion dollar backlog of maintenance and repairs. This total was increased in May of 1990 to a value of 80 to 90 billion, when follow-up analyses identified additional requirements.⁽⁶⁾ This amount represents an average deficiency of over 25% when expressed as a

percentage of the total replacement costs, estimated at over 300 billion dollars, of all campus buildings nationwide.

The University of Georgia Survey

As a Research (Carnegie category) Institution with more than 80% of its buildings older than 20 years, the University of Georgia would be expected to experience a deficiency higher than 25%, caused not only by building age, but also by the increased level of sophistication of research building systems and by expanded usage of these facilities due to increased enrollments. The recent survey conducted by the University confirms this condition, indicating a gross deficiency of over 29% of replacement costs for all 1,118 buildings carried on the University space inventory. Note that Housing Buildings have a gross deficiency higher than the average of all buildings, while Resident Instruction Buildings have a deficiency percentage slightly lower than average.

Survey Instrument

The building condition survey is based on Dr. Harlan Bareither's deficiency model developed at the University of Illinois; this method separates building deficiencies into seven general headings. Dr. Bareither pioneered research in facility space planning in the late 1960s, and published the seminal work in this area.⁽⁷⁾ He suggested that the University of Georgia

employ a building evaluation model which stressed deficiencies, represented as a percentage of building replacement costs; this procedure utilized a two page survey instrument (see Appendix I). Replacement costs for each building were estimated, using square foot costs from recently constructed buildings, national estimating data, and costs generated by the NACUBO/APPA National Survey. Each week appropriate personnel were given a list of buildings to review and estimate deficiencies for each category. Costs were transferred to deficiency percentages: e.g., for a building with a replacement value of \$100,000, each percentage replacement is worth \$1,000; if the air conditioning system had a deficiency which would cost \$5,100 to correct, it was given a deficiency rating of 5.1 for that category.

Weekly meetings, lasting about 3 hours each, were held over several months to collect data. Representatives of Physical Plant, Institutional Research and Planning, and the Departments occupying each building met and estimated, on a building by building basis, the dollar value of all necessary capital renewal and deferred maintenance work. This amount was compared to the total replacement value of the building, and the resultant percentage deficiency was recorded. Since many institutions are funded on a formula basis using a similar percentage (i.e. with capital renewal/deferred maintenance funded on a line item as a percentage of replacement cost), a direct comparison between actual funding percentage and deficiency percentage can be made.

For example, the University System of Georgia Resident Instruction funding formula returns to the University of Georgia 3/4 of one percent of total building replacement cost. It takes no effort to see that a present deficiency of almost 30% is not going to be corrected by a yearly funding level of 0.75%.

Survey Results

The University of Georgia has 1,118 buildings, with a total area of over eleven million square feet. A review of the summary sheet (Appendix II-A) for all Buildings indicates several areas of significant deficiencies:

A. In category 30 - Exterior: roof and window replacements total over 19 million dollars.

B. In category 40 - General: New fixed equipment and elevators total over 36 million dollars, and new interior wall realignment costs exceed 23 million dollars.

C. In category 50 - Plumbing/Fire Protection: waste piping and sprinkler systems total over 22 million dollars.

D. In category 60 - Heating, Ventilating and Air Conditioning: replacement of systems, equipment and controls account for almost 79 million dollars.

E. In category 70 - Electrical: new distribution (wiring) and fire alarms total almost 22 million dollars.

Data covering the evaluation of Main Campus Resident Instruction Buildings (Appendix II-B) and Main Campus Housing

Buildings (Appendix II-C) indicates interesting similarities and differences in the various categories. Appendix III summarizes the data for all Buildings, Resident Instruction Buildings and Housing Buildings. In addition, individual summary sheets are included in Appendix IV, covering a "benign" older building (LeConte Hall [1938] - History Department - Appendix IV-A), a typical dormitory (Boggs Hall [1961] - Appendix IV-B), and a large Research Building (Boyd Graduate Studies Building [1968] - Appendix IV-C).

Implications for Colleges and Universities

A majority of college and university buildings nationwide would be expected to evidence high deficiency percentages similar to those revealed by the University of Georgia survey. Housing buildings are particularly affected by this capital renewal/deferred maintenance problem, since the appearance and condition of these structures is important for recruitment and retention of students. Many housing facilities at the University of Georgia were built without air conditioning in the 1950s and 60s; correcting oversights like these accounts for a high percentage of the total deficiency in housing buildings. In addition, experts suggest that Housing buildings should be renewed on a ten-year cycle, which further exacerbates the problem.⁽⁸⁾

All institutions should consider performing a building evaluation survey to identify their exact deficiency needs, and

then follow the guidelines proposed in the current literature. In late 1989, NACUBO, APPA and the Society for College and University Planning (SCUP) joined forces to recommend the following solution to the dilemma, based on financial equilibrium planning concepts:⁽⁹⁾

- Sufficient "plant renewal" funds on an ongoing basis to keep the plant in good condition for its present use, based on facility subsystem life cycles. (1.5 to 2.5 percent of plant replacement costs for most institutions).
- And sufficient "plant adaptation" funds on an ongoing basis to alter the physical plant for changes in use and changes in codes and standards, based on recent experience and judgment (0.5 to 1.5 percent of plant replacement costs at most institutions).
- And sufficient "catch-up maintenance" funds over a short term period to bring the plant into reliable operating condition, based on a facilities audit".

Regardless of funding level, projects should be prioritized and scheduled over several fiscal years to achieve maximum efficiency and effectiveness. Predictive models, such as Cushing Phillip's formula approach⁽¹⁰⁾, should be employed for this purpose.

Conclusion

The building condition evaluation survey described in this paper was based on the Bareither deficiency model. This assessment method is very thorough and is highly recommended for use by other institutions. However, this is not the only model available; others may be more appropriate for other institutions.

Regardless of the model used, all members of the academy should consider implementing an audit as soon as possible. In addition, a joint venture involving Instructional Research and Physical Plant personnel should also be considered to perform this evaluation.

Finally, all institutions of higher education must be sensitive to these building issues, mundane as they may be, because we have failed in the stewardship of these facilities.⁽¹¹⁾ The President of the Carnegie Foundation reminded us recently why we must do better:

The buildings we erect today also reflect our priorities as people. And as we invest in education - as we build our cathedrals of learning - we are, in fact, affirming the university as a place where civilization will be preserved, where learning will be highly prized, and where the potentialities of every student will be served.⁽¹²⁾

Footnotes

- (1) Rush, Sean C. and Johnson, Sandra L. The Decaying American Campus-A Ticking Time Bomb. Alexandria, VA:APPA, 1989, p. 135.
- (2) *ibid.*, p. 134
- (3) *ibid.*, p. 135
- (4) Kaiser, Harvey H. Facilities Audit Workbook. Washington, D.C.:APPA, 1987, p. 10.
- (6) Rush, loc. cit., p. 12.
- (6) Schaw, Walter A. "APPA Fact File - Current Status of 'The Decaying American Campus'". Alexandria, VA:APPA, 1990.
- (7) Bareither, Harlan D. and Schillinger, Jerry L. University Space Planning. Urbana, IL:University of Illinois Press, 1968.
- (8) Reed, William S. "Private Institution Approaches". In Meyerson, Jowel W. and Peter M. Mitchell. Financing Capital Maintenance. Washington, D.C.:NACUBO, 1990.
- (9) Dunn, John A. "Financial Planning Guidelines". In "Capital Renewal and Deferred Maintenance", Critical Issues in Facilities Management Series (No. 4). Alexandria, Va.: APPA, 1989. Dunn presented this summary information from the recently published NACUBO/APPA/SCUP Financial Planning Guidelines for Facility Renewal and Adaption. Ann Arbor:SCUP, 1989. For a good overall view of the problems faced by the academy see Harvey H. Kaiser, editor. "Planning and Managing Higher Educational Facilities", New Directions for Institutional Research. San Francisco: Jossey-Bass, 1989.
- (10) The Phillips model is described in Kaiser, Harvey H. "Major Maintenance and Capital Renewal/Replacement Programs", in Dillow, Rex O. (ed) Facilities Management - A Manual for Plant Administration (2nd ed.). Alexandria, Va.: APPA, 1989.
- (11) In the Executive Summary of Financial Planning Guidelines for Facility Renewal and Adaption, the only italicized sentence is "It has become clear that American higher education has failed in the stewardship of its facilities assets."
- (12) Boyer, Ernest L. "Buildings Reflect Our Priorities". Educational Record, Winter 1989 (Special Reprint by A.C.E.), p. 27.

Selected Bibliography

- Abramson, Paul. "A Window of Opportunity". American School and University. September, 1989.
- American Council on Education. "Rebuilding the Campus". (Focus issue on college campuses). Educational Record, Winter 1989.
- Association of Governing Boards of Universities and Colleges. Financial Responsibilities of Governing Boards. Washington, D.C.: AGB, 1985.
- Association of Physical Plant Administrators. Comparative Costs and Staffing Report (1987-88). Alexandria, Virginia: APPA, 1988.
- _____. Executive Briefing: The Decaying American Campus. (Videotape). Alexandria, Virginia. APPA, 1989.
- _____. "Capital Renewal and Deferred Maintenance". Critical Issues in Facilities Management Series (no. 4). Alexandria, Virginia: APPA, 1989.
- _____. "Schools' Looks Draw Students." APPA Newsletter, November, 1986.
- _____. "Bennett Calls for Student Aid Cuts: Deferred Maintenance Costs Not Acceptable Excuse, Says Education Secretary." APPA Newsletter, January 1987.
- _____. "Higher Ed Presidents Told of Deferred Maintenance Challenges." APPA Newsletter, November 1987.
- _____. "Facilities Named as Education Issue in '88 Election." APPA Newsletter, February 1988.
- Bareither, Harlan D. "Projection of Physical Facilities for Research Activity." Planning for Higher Education 15:2 (1987).
- Bareither, Harlan D. and Schillinger, Jerry L. University Space Planning. Urbana, IL.:University of Illinois Press, 1968.
- Bowen, Howard R. The Costs of Higher Education. San Francisco: Jossey-Bass, 1980.
- Boyer, Ernest L. "Facilities and the Academic Mission." Facilities Manager, Winter 1988.
- Calgaard, Dr. Ronald. "The View from the Top: A President Looks at Facilities Management." Facilities Manager, Winter 1987.

- Christensen, Douglas K. "Integrating Capital Studies Within Physical Plant Operations." Facilities Manager, Fall 1986.
- Dillow, Rex O. (ed.). Facilities Management - A Manual for Plant Administration (Second Edition). Alexandria, Virginia: APPA, 1989.
- Dozier, Jack et al. Operational Planning and Budgeting for Colleges. Washington, D.C. NACUBO, 1988
- Forrester, Robert T. Handbook on Debt Management for Colleges and Universities. Washington, D.C.: NACUBO, 1988.
- Graves, Ben E. "Providing Ammunition for Facility Improvement." American School and University. June, 1989.
- Halpern, Sheldon. "Why Old Main Looks So Shabby." Chronicle of Higher Education, May 19, 1982.
- Hug, Jack. "University Facilities and Equipment: Inseparable Assets, Potential Liabilities." Facilities Manager, Spring 1989.
- Jaschik, Scott. "For Many Public Colleges, Construction and Renovation Are Now Top Priorities." Chronicle of Higher Education, March 23, 1988.
- Jenny, Hans H. et al. Hang-Gliding or Looking for an Updraft. A Study of College and University Finance in the 1980's - The Capital Margin. Wooster, Ohio: The College of Wooster. 1981.
- Kaiser, Harvey H. "Capital Needs in Higher Education." Facilities Manager, Summer 1987.
- _____. Mortgaging the Future: The Cost of Deferring Maintenance. Washington, D.C.: APPA, 1979.
- _____. Crumbling Academe - Solving the Capital Renewal and Replacement Dilemma. Washington, D.C. Association of Governing Boards of Universities and Colleges, 1984.
- _____. (ed.). Planning and Managing Higher Education Facilities. New Directions for Institutional Research (no. 61). Jossey-Bass, 1989.
- _____. Facilities Audit Workbook. Washington, D.C.: APPA, 1982.
- _____. "Funding of Facility Repairs and Renovations." Business Officer, January, 1982.
- Leslie, Larry L. (ed.). Responding to New Realities in Funding. San Francisco: Jossey-Bass, 1984.

- Meisinger, Richard J. and Dubeck, Leroy W. College and University Budgeting. Washington, D.C. National Association of Colleges and University Business Officers, 1984.
- Meyerson, Joel W. "Top Ten Concerns for Trustees in 1988". AGB-Reports, March/April, 1988.
- Middleton, William D. "Comprehensive Facilities Management" in Harvey Kaiser (ed.) Planning and Managing Higher Educational Facilities. San Francisco: Jossey-Bass, 1989.
- National Association of College and University Business Officers. Capital Formation Alternatives in Higher Education. Washington, D.C.: NACUBO, 1988.
- National Science Foundation. Scientific and Engineering Research Facilities at Colleges and Universities, 1988. Washington, D.C.: NAF, 1988.
- Phillips, Cushing Jr. "Facilities Renewal: The Formula Approach." In Proceedings of the 73rd Annual Meeting. Alexandria, Virginia: APPA, 1986.
- Robinson, Daniel D. Capital Maintenance for Colleges and Universities. Washington, D.C.: NACUBO, 1986.
- Rush, Sean C. and Johnson, Sandra L. The Decaying American Campus: A Ticking Time Bomb. Alexandria, Virginia: APPA, 1989.
- Saber, Terry L. "Coping With Deferred Maintenance." Business Officer, May, 1982.
- State Higher Education Executive Officers. Creative Financing for Higher Education Facilities and Equipment. Denver, Co. 1985.
- Walzenbach, Lanora F. (ed.). College and University Business Administration. Washington, D.C.: NACUBO, 1982 (4th edition).
- Wilson, Linda S. "Planning For Excellence: The Capital Facilities Dilemma in the American Graduate School." Planning for Higher Education Vol 15, No. 1, 1986-87.

**UNIVERSITY OF GEORGIA
BUILDING CONDITION EVALUATION**

BUILDING _____ NO. _____ CAMPUS _____ DATE CONSTR. _____
GROSS AREA _____ EST. REPLACEMENT COST _____

EACH DEDUCT POINT EQUALS APPROXIMATELY _____ DEDUCT POINTS
EVALUATION FACTORS AND CONDITIONS NOTES COMMENTS

1.0 FOUNDATION**MAXIMUM 8 POINTS**

1.1 Cracked Foundation Deduct up to 3 pts _____

1.2 Apparent Settlement Deduct up to 5 pts _____

1.3 Other Problems _____

Note: If major settlement is apparent, indicate if opinion of Structural Engineer is required

2.0 SUPERSTRUCTURE**MAXIMUM 13 POINTS**

2.1 Broken or Cracked Walls Deduct up to 5 pts _____

2.2 Roof Sagging Deduct up to 3 pts _____

2.3 Floor Movement Excessive Deduct up to 4 pts _____

2.4 Roof Ponds Deduct up to 1 pt _____

2.5 Other Problems _____

3.0 EXTERIOR SKIN**MAXIMUM 11 POINTS**

3.1 Needs New Roof Deduct up to 3 pts _____

3.2 Windows in Poor Condition Deduct up to 4 pts _____

3.3 Tuckpointing Required Deduct up to 4 pts _____

3.4 Other Problems _____

4.0 GENERAL**MAXIMUM 29 POINTS**

4.1 Interior Needs Painting Deduct up to 2 pts _____

4.2 Needs New Flooring Deduct up to 2 pts _____

4.3 Needs New Ceiling Deduct up to 1 pt _____

4.4 Inter. Walls Need Realign. Deduct up to 16 pts _____

4.5 Needs New Fixed Equipment Deduct up to 8 pts _____

4.6 Exits & Stairways _____

4.7 Entry Ramp _____

4.8 Elevator _____

4.9 Other Problems _____

4.9A Asbestos _____

BUILDING _____ NO. _____

5.0 PLUMBING AND FIRE PROTECTION SYSTEMS MAXIMUM 6 POINTS

5.1 Fixture Replacement	Deduct up to 1 pt	_____
5.2 Needs New Waste & Vent	Deduct up to 2 pts	_____
5.3 Water Line Capacity Inadeq.	Deduct up to 1 pt	_____
5.4 Sprinkler System	Deduct up to 2 pts	_____
5.5 Handicap Access. Toilets		_____
5.6 Other Problems		_____

6.0 HEATING, VENTILATION, AND MAXIMUM 20 POINTS
AIR-CONDITIONING SYSTEMS

6.1 Heating	Deduct up to 5 pts	_____
6.2 Ventilation	Deduct up to 6 pts	_____
6.3 Air Conditioning	Deduct up to 7 pts	_____
6.4 Temperature Control	Deduct up to 2 pts	_____
6.5 Other Problems		_____

7.0 ELECTRICAL, FIRE ALARM, AND MAXIMUM 13 POINTS
LIGHTING SYSTEMS

7.1 Capacity	Deduct up to 1 pt	_____
7.2 Distribution	Deduct up to 10 pts	_____
7.3 Fixtures	Deduct up to 1 pt	_____
7.4 Fire Alarm System	Deduct up to 1 pt	_____
7.5 Other Problems		_____

8.0 TOTAL BUILDING DEFICIENCY**9.0 COMMENTS:**

EVALUATORS: _____

DATE _____

UNIVERSITY OF GEORGIA
INSTITUTIONAL RESEARCH AND PLANNING
BUILDING CONDITION EVALUATION SUMMARY

SEP 27, 1990

PAGE 1

BUILDING NAME	TOTAL	EST CORRECTION	X OF EST
LOCATION	ALL	COST	REP COST
CONSTRUCTION DATE	ALL		
EVALUATION DATE	ALL		
10 FOUNDATION		7,196,423	.66
11 CRACKED FOUNDATION		2,139,442	.20
12 APPARENT SETTLEMENT		3,075,787	.20
13 OTHER PROBLEMS		1,981,194	.10
20 SUPERSTRUCTURE		16,511,627	1.52
21 BROKEN OR CRACKED WALLS		6,926,898	.64
22 ROOF SAGGING		1,394,789	.13
23 FLOOR MOVEMENT EXCESSIVE		3,141,864	.29
24 ROOF PONDS		891,127	.08
25 OTHER PROBLEMS		4,156,949	.38
30 EXTERIOR SKIN		26,879,684	2.47
31 NEEDS NEW ROOF		8,774,930	.81
32 WINDOWS IN POOR CONDITION		10,400,606	.95
33 TUCKPOINTING REQUIRED		2,782,768	.26
34 OTHER PROBLEMS		4,921,380	.45
40 GENERAL		112,089,036	10.29
41 INTERIOR NEEDS PAINTING		7,098,487	.73
42 NEEDS NEW FLOORING		8,893,371	.82
43 NEEDS NEW CEILING		6,540,421	.60
44 INTERIOR WALLS NEED REALIGN		23,090,080	2.12
45 NEEDS NEW FIXED EQUIPMENT		26,603,761	2.44
46 EXITS AND STAIRWAYS		5,729,605	.53
47 ENTRY RAMP		1,350,699	.12
48 ELEVATOR		9,490,952	.87
49 OTHER PROBLEMS		8,207,660	.75
49A ASBESTOS		14,284,037	1.31
50 PLUMBING & FIRE PROTECTION SYS		42,087,007	3.86
51 FIXTURE REPLACEMENT		6,598,017	.61
52 NEEDS NEW WASTE AND VENT		9,129,597	.84
53 WATER LINE CAPACITY INADEQUATE		6,965,641	.64
54 SPRINKLER SYSTEM		13,090,824	1.20
55 HANDICAP ACCESS - TOILETS		4,075,464	.37
56 OTHER PROBLEMS		2,227,464	.20
60 HEATING, VENTILATION & AC SYS		83,740,551	7.69
61 HEATING		17,677,135	1.62
62 VENTILATION		24,344,200	2.23
63 AIR CONDITIONING		28,372,638	2.60
64 TEMPERATURE CONTROL		8,497,505	.78
65 OTHER PROBLEMS		4,849,073	.45
70 ELECT, FIRE ALARM & LIGHT SYS		33,410,988	3.07
71 CAPACITY		4,986,500	.45
72 DISTRIBUTION		17,414,850	1.60
73 FIXTURES		4,673,540	.43
74 FIRE ALARM SYSTEM		4,499,773	.41
75 OTHER PROBLEMS		1,916,325	.18
80 TOTAL BUILDING DEFICIENCY		321,918,159	29.55

NUMBER OF BUILDINGS 1,110
GROSS AREA 11,063,374
EST. REPLACEMENT COST 1,089,299,869

UNIVERSITY OF GEORGIA
INSTITUTIONAL RESEARCH AND PLANNING
BUILDING CONDITION EVALUATION SUMMARY

SEP 27, 1990

PAGE 1

RESIDENT INSTRUCTION

BUILDING NAME	TOTAL
LOCATION	816 UGA MAIN CAMPUS
CONSTRUCTION DATE	ALL
EVALUATION DATE	ALL

	EST CORRECTION COST	% OF EST REP COST
10 FOUNDATION	4,240,190	.62
11 CRACKED FOUNDATION	1,150,907	.17
12 APPARENT SETTLEMENT	1,593,290	.23
13 OTHER PROBLEMS	1,407,913	.22
20 SUPERSTRUCTURE	9,030,857	1.44
21 BROKEN OR CRACKED WALLS	3,906,215	.57
22 ROOF SAGGING	553,479	.08
23 FLOOR MOVEMENT EXCESSIVE	2,280,225	.34
24 ROOF PONDS	566,145	.08
25 OTHER PROBLEMS	2,524,794	.37
30 EXTERIOR SKIN	13,311,346	1.96
31 NEEDS NEW ROOF	4,975,843	.73
32 WINDOWS IN POOR CONDITION	5,294,953	.78
33 TUCKPOINTING REQUIRED	1,002,910	.26
34 OTHER PROBLEMS	1,237,640	.18
40 GENERAL	75,677,588	11.12
41 INTERIOR NEEDS PAINTING	3,988,249	.59
42 NEEDS NEW FLOORING	5,608,731	.82
43 NEEDS NEW CEILING	4,264,962	.63
44 INTERIOR WALLS NEED REALIGN	17,096,621	2.51
45 NEEDS NEW FIXED EQUIPMENT	19,215,609	2.82
46 EXITS AND STAIRWAYS	3,634,041	.53
47 ENTRY RAMP	969,003	.14
48 ELEVATOR	6,444,305	.95
49 OTHER PROBLEMS	3,363,411	.49
49A ASBESTOS	11,092,579	1.63
50 PLUMBING & FIRE PROTECTION SYS	25,026,940	3.79
51 FIXTURE REPLACEMENT	3,925,659	.58
52 NEEDS NEW WASTE AND VENT	5,348,556	.79
53 WATER LINE CAPACITY INADEQUATE	3,905,309	.57
54 SPRINKLER SYSTEM	8,722,555	1.28
55 HANDICAP ACCESS - TOILETS	2,945,908	.43
56 OTHER PROBLEMS	978,955	.14
60 HEATING, VENTILATION & AC SYS	49,528,622	7.28
61 HEATING	9,750,903	1.43
62 VENTILATION	14,853,415	2.18
63 AIR CONDITIONING	16,741,107	2.46
64 TEMPERATURE CONTROL	5,315,909	.78
65 OTHER PROBLEMS	2,067,129	.42
70 ELECT, FIRE ALARM & LIGHT SYS	20,094,190	3.07
71 CAPACITY	3,293,644	.48
72 DISTRIBUTION	10,756,536	1.58
73 FIXTURES	3,294,894	.48
74 FIRE ALARM SYSTEM	2,475,331	.36
75 OTHER PROBLEMS	1,073,707	.16
80 TOTAL BUILDING DEFICIENCY	199,309,736	29.29

NUMBER OF BUILDINGS	104
GROSS AREA	5,744,000
EST. REPLACEMENT COST	600,553,462

20 APPENDIX II-B
P - 18

UNIVERSITY OF GEORGIA
INSTITUTIONAL RESEARCH AND PLANNING
BUILDING CONDITION EVALUATION SUMMARY

SEP 27, 1990

PAGE 1

BUILDING NAME	TOTAL		
LOCATION	816B RESIDENTIAL UGA MAIN CAMPUS		
CONSTRUCTION DATE	ALL		
EVALUATION DATE	ALL		
	EST CORRECTION	% OF EST	
	COST	REP COST	
10 FOUNDATION	559,309	.31	
11 CRACKED FOUNDATION	101,090	.06	
12 APPARENT SETTLEMENT	322,722	.18	
13 OTHER PROBLEMS	135,497	.08	
20 SUPERSTRUCTURE	1,772,124	.99	
21 BROKEN OR CRACKED WALLS	1,210,305	.68	
22 ROOF SAGGING	72,420	.04	
23 FLOOR MOVEMENT EXCESSIVE	148,016	.08	
24 ROOF PONDS	50,021	.03	
25 OTHER PROBLEMS	291,362	.16	
30 EXTERIOR SKIN	5,626,602	3.15	
31 NEEDS NEW ROOF	946,144	.53	
32 WINDOWS IN POOR CONDITION	3,026,030	1.70	
33 TUCKPOINTING REQUIRED	308,067	.17	
34 OTHER PROBLEMS	1,346,441	.75	
40 GENERAL	14,703,627	8.24	
41 INTERIOR NEEDS PAINTING	1,543,701	.87	
42 NEEDS NEW FLOORING	1,729,722	.97	
43 NEEDS NEW CEILING	1,277,747	.72	
44 INTERIOR WALLS NEED REALIGN	1,265,303	.71	
45 NEEDS NEW FIXED EQUIPMENT	2,517,203	1.41	
46 EXITS AND STAIRWAYS	1,140,347	.64	
47 ENTRY RAMP	108,271	.11	
48 ELEVATOR	2,413,911	1.35	
49 OTHER PROBLEMS	1,260,708	.71	
49A ASBESTOS	1,366,634	.77	
50 PLUMBING & FIRE PROTECTION SYS	8,384,601	4.70	
51 FIXTURE REPLACEMENT	1,490,277	.84	
52 NEEDS NEW WASTE AND VENT	2,081,799	1.17	
53 WATER LINE CAPACITY INADEQUATE	1,433,674	.80	
54 SPRINKLER SYSTEM	2,418,450	1.36	
55 HANDICAP ACCESS - TOILETS	309,432	.17	
56 OTHER PROBLEMS	650,961	.36	
60 HEATING, VENTILATION & AC SYS	19,895,013	11.15	
61 HEATING	4,535,988	2.54	
62 VENTILATION	5,715,123	3.20	
63 AIR CONDITIONING	6,635,410	3.72	
64 TEMPERATURE CONTROL	1,764,664	.99	
65 OTHER PROBLEMS	1,244,620	.70	
70 ELECT, FIRE ALARM & LIGHT SYS	4,517,387	2.53	
71 CAPACITY	775,672	.43	
72 DISTRIBUTION	2,235,359	1.25	
73 FIXTURES	480,426	.27	
74 FIRE ALARM SYSTEM	907,904	.51	
75 OTHER PROBLEMS	110,026	.07	
80 TOTAL BUILDING DEFICIENCY	55,459,539	31.09	

NUMBER OF BUILDINGS 48
GROSS AREA 2,043,141
EST. REPLACEMENT COST 178,402,005

APPENDIX II-C

P - 19

APPENDIX III - SUMMARY

BUILDING CONDITION EVALUATION - UNIVERSITY OF GEORGIA

1. <u>General</u>	<u>All Buildings</u>	<u>Housing Main Campus</u>	<u>Resident Instruction Main Campus</u>
Buildings	1,118	48	184
Gross Area (Sq. Ft.)	11,063,376	2,043,141	5,744,888
Replacement Cost	\$1,089,299,869	\$178,402,005	\$680,553,462

2. SURVEY RESULTS (Bareither Deficiency Model)

<u>Category</u>	<u>All Buildings Deficiency %</u>	<u>Housing Main Campus</u>	<u>Resident Instruction Main Campus</u>
10 - Foundations	.66	.31	.62
20 - Superstructure	1.52	.99	1.44
30 - Exterior	2.47	3.15	1.96
40 - General	10.29	8.24	11.12
50 - Plumbing/Fire	3.86	4.70	3.79
60 - HVAC	7.69	11.15	7.28
70 - Electrical	<u>3.07</u>	<u>2.53</u>	<u>3.07</u>
80 - Total (Gross)	29.55%	31.09%	29.29%

3. Gross Deficiencies (\$): (Replacement Cost x Gross Deficiency %)

a) All Buildings: \$1,089,299,869 x 29.55% = \$321,915,159

b) Main Campus Housing Buildings: \$178,402,005 x 31.09% = \$55,459,539

c) Main Campus Resident Instruction Buildings: \$680,553,462 x 29.29% = \$199,309,736

UNIVERSITY OF GEORGIA
INSTITUTIONAL RESEARCH AND PLANNING
BUILDING CONDITION EVALUATION
BY BUILDING NUMBER

JAN 30, 1990

PAGE 19

BUILDING NAME LECONTE HALL
BUILDING NUMBER 0055
LOCATION 816A UGA MAIN CAMPUS
DATE CONSTRUCTED 1938
GROSS AREA 28,330
EST. REPLACEMENT COST 3,314,610
EVALUATION DATE 1989 02 21

	EST CORRECTION COST	% OF EST REP COST
10 FOUNDATION		.0
11 CRACKED FOUNDATION		.0
12 APPARENT SETTLEMENT		.0
13 OTHER PROBLEMS		.0
20 SUPERSTRUCTURE	49,719	1.5
21 BROKEN OR CRACKED WALLS	33,146	1.0
22 ROOF SAGGING		.0
23 FLOOR MOVEMENT EXCESSIVE		.0
24 ROOF PONDS	16,573	.5
25 OTHER PROBLEMS		.0
30 EXTERIOR SKIN	165,730	5.0
31 NEEDS NEW ROOF	33,146	1.0
32 WINDOWS IN POOR CONDITION	132,584	4.0
33 TUCKPOINTING REQUIRED		.0
34 OTHER PROBLEMS		.0
40 GENERAL	430,899	13.0
41 INTERIOR NEEDS PAINTING	16,573	.5
42 NEEDS NEW FLOORING	66,292	2.0
43 NEEDS NEW CEILING	33,146	1.0
44 INTERIOR WALLS NEED REALIGN	33,146	1.0
45 NEEDS NEW FIXED EQUIPMENT	16,573	.5
46 EXITS AND STAIRWAYS	33,146	1.0
47 ENTRY RAMP		.0
48 ELEVATOR	198,877	6.0
49 OTHER PROBLEMS		.0
49A ASBESTOS	33,146	1.0
50 PLUMBING & FIRE PROTECTION SYS	92,809	2.8
51 FIXTURE REPLACEMENT	9,944	.3
52 NEEDS NEW WASTE AND VENT	9,944	.3
53 WATER LINE CAPACITY INADEQUATE	13,258	.4
54 SPRINKLER SYSTEM	49,719	1.5
55 HANDICAP ACCESS - TOILETS	9,944	.3
56 OTHER PROBLEMS		.0
60 HEATING, VENTILATION & AC SYS	397,753	12.0
61 HEATING	66,292	2.0
62 VENTILATION	99,438	3.0
63 AIR CONDITIONING	198,877	6.0
64 TEMPERATURE CONTROL	33,146	1.0
65 OTHER PROBLEMS		.0
70 ELECT, FIRE ALARM & LIGHT SYS	43,090	1.3
71 CAPACITY	9,944	.3
72 DISTRIBUTION	9,944	.3
73 FIXTURES	16,573	.5
74 FIRE ALARM SYSTEM	6,629	.2
75 OTHER PROBLEMS		.0
80 TOTAL BUILDING DEFICIENCY	1,180,001	35.6

23

APPENDIX IV-A

P - 21

BEST COPY AVAILABLE

UNIVERSITY OF GEORGIA
INSTITUTIONAL RESEARCH AND PLANNING
BUILDING CONDITION EVALUATION
BY BUILDING NUMBER

JAN 30, 1990

PAGE 164

BUILDING NAME DOGGS HALL
BUILDING NUMBER 2216
LOCATION 816B RESIDENTIAL UGA MAIN CAMPUS
DATE CONSTRUCTED 1961
GROSS AREA 32,638
EST. REPLACEMENT COST 2,611,040
EVALUATION DATE 1989 05 02

	EST CORRECTION COST	% OF EST REP COST
10 FOUNDATION		.0
11 CRACKED FOUNDATION		.0
12 APPARENT SETTLEMENT		.0
13 OTHER PROBLEMS		.0
20 SUPERSTRUCTURE	26,110	1.0
21 BROKEN OR CRACKED WALLS	26,110	1.0
22 ROOF SAGGING		.0
23 FLOOR MOVEMENT EXCESSIVE		.0
24 ROOF PONDS		.0
25 OTHER PROBLEMS		.0
30 EXTERIOR SKIN	78,331	3.0
31 NEEDS NEW ROOF		.0
32 WINDOWS IN POOR CONDITION	26,110	1.0
33 TUCKPOINTING REQUIRED	13,055	.5
34 OTHER PROBLEMS	39,166	1.5
40 GENERAL	193,216	7.4
41 INTERIOR NEEDS PAINTING	26,110	1.0
42 NEEDS NEW FLOORING	52,221	2.0
43 NEEDS NEW CEILING	26,110	1.0
44 INTERIOR WALLS NEED REALIGN	26,110	1.0
45 NEEDS NEW FIXED EQUIPMENT		.0
46 EXITS AND STAIRWAYS	13,055	.5
47 ENTRY RAMP	13,055	.5
48 ELEVATOR		.0
49 OTHER PROBLEMS		.0
49A ASBESTOS	36,555	1.4
50 PLUMBING & FIRE PROTECTION SYS	130,550	5.0
51 FIXTURE REPLACEMENT	26,110	1.0
52 NEEDS NEW WASTE AND VENT	26,110	1.0
53 WATER LINE CAPACITY INADEQUATE	26,110	1.0
54 SPRINKLER SYSTEM		.0
55 HANDICAP ACCESS - TOILETS	26,110	1.0
56 OTHER PROBLEMS	26,110	1.0
60 HEATING, VENTILATION & AC SYS	522,208	20.0
61 HEATING	130,552	5.0
62 VENTILATION	156,662	6.0
63 AIR CONDITIONING	182,773	7.0
64 TEMPERATURE CONTROL	52,221	2.0
65 OTHER PROBLEMS		.0
70 ELECT, FIRE ALARM & LIGHT SYS	26,110	1.0
71 CAPACITY	5,222	.2
72 DISTRIBUTION	7,833	.3
73 FIXTURES	5,222	.2
74 FIRE ALARM SYSTEM	7,833	.3
75 OTHER PROBLEMS		.0
80 TOTAL BUILDING DEFICIENCY	976,529	37.4

UNIVERSITY OF GEORGIA
INSTITUTIONAL RESEARCH AND PLANNING
BUILDING CONDITION EVALUATION
BY BUILDING NUMBER

JAN 30, 1990

PAGE 70

BUILDING NAME BOYD GRAD RSCH CTR
BUILDING NUMBER 1023
LOCATION 816A UGA MAIN CAMPUS
DATE CONSTRUCTED 1968
GROSS AREA 159,517
EST. REPLACEMENT COST 21,375,270
EVALUATION DATE 1989 03 21

	EST CORRECTION COST	% OF EST REP COST
10 FOUNDATION		.0
11 CRACKED FOUNDATION		.0
12 APPARENT SETTLEMENT		.0
13 OTHER PROBLEMS		.0
20 SUPERSTRUCTURE	897,762	4.2
21 BROKEN OR CRACKED WALLS	427,506	2.0
22 ROOF SAGGING		.0
23 FLOOR MOVEMENT EXCESSIVE		.0
24 ROOF PONDS		.0
25 OTHER PROBLEMS	470,256	2.2
30 EXTERIOR SKIN	106,876	.5
31 NEEDS NEW ROOF	106,876	.5
32 WINDOWS IN POOR CONDITION		.0
33 TUCKPOINTING REQUIRED		.0
34 OTHER PROBLEMS		.0
40 GENERAL	1,474,895	6.9
41 INTERIOR NEEDS PAINTING	128,252	.6
42 NEEDS NEW FLOORING	106,876	.5
43 NEEDS NEW CEILING	106,876	.5
44 INTERIOR WALLS NEED REALIGN	427,506	2.0
45 NEEDS NEW FIXED EQUIPMENT	213,753	1.0
46 EXITS AND STAIRWAYS	64,126	.3
47 ENTRY RAMP		.0
48 ELEVATOR	213,753	1.0
49 OTHER PROBLEMS		.0
49A ASBESTOS	213,753	1.0
50 PLUMBING & FIRE PROTECTION SYS	1,282,518	6.0
51 FIXTURE REPLACEMENT	213,753	1.0
52 NEEDS NEW WASTE AND VENT	213,753	1.0
53 WATER LINE CAPACITY INADEQUATE	213,753	1.0
54 SPRINKLER SYSTEM	427,506	2.0
55 HANDICAP ACCESS - TOILETS	213,753	1.0
56 OTHER PROBLEMS		.0
60 HEATING, VENTILATION & AC SYS	897,763	4.2
61 HEATING	213,753	1.0
62 VENTILATION	213,753	1.0
63 AIR CONDITIONING	213,753	1.0
64 TEMPERATURE CONTROL	42,751	.2
65 OTHER PROBLEMS	213,753	1.0
70 ELECT, FIRE ALARM & LIGHT SYS	1,432,144	6.7
71 CAPACITY	106,876	.5
72 DISTRIBUTION	427,506	2.0
73 FIXTURES	42,751	.2
74 FIRE ALARM SYSTEM	106,876	.5
75 OTHER PROBLEMS	748,135	3.5
80 TOTAL BUILDING DEFICIENCY	6,891,954	28.5

25